







Takeoff Tab

Keehi Lagoon Samll Boat Harbour parking and pavement







Bid No. 68

No.	Name	Height	Area	Quantity1	UOM1	Quantity2	UOM2	Quantity3	UOM3
Pavements									
	3	Existed A.C Pavement Removed and Replaced with 3" Thick	0"	Area 1	1,623.74 SY	0		0	
	1	New AC (State Mix IV) with 3 " Thick	0"	Multi-Area Total	1,279.46 SY	0		0	
				Area 1	768.12 SY	0		0	
				Area 2	511.35 SY	0		0	
Base Course									
	6	6" thk Base Course @ Existing	0"	Area 1	1,623.74 SY	0		0	
	2	Compacted Base Course Min 6" Thick @ New AC	0"	Multi-Area Total	1,279.73 SY	0		0	
				Area 1	768.55 SY	0		0	
				Area 2	511.18 SY	0		0	
Stripes									
	5	12" Wide White Stripes	0"	Area 1	118.94 LF	0		0	
	4	4" Wide White Stripes	0"	Multi-Area Total	1,160.51 LF	0		0	
				Area 1	898.77 LF	0		0	
				Area 2	261.74 LF	0		0	

Worksheet Tab

Keehi Lagoon Samll Boat Harbour parking and pavement

Bid No. 68

No.	Name	Qty1	UOM1	Qty2	UOM2	Qty3	UOM3	Mat.(\$)	Labor(\$)	Sub(\$)	Total(\$)
Base Course											
	2 Compacted Base Course Min 6" Thick @ New AC	1,280	SY					0.00	0.00	0.00	0.00
	6 6" thk Base Course @ Existing	1,624	SY					0.00	0.00	0.00	0.00
Pavements											
	1 New AC (State Mix IV) with 3 " Thick	1,279	SY					0.00	0.00	0.00	0.00
	3 Existed A.C Pavement Removed and Replaced with 3" Thick	1,624	SY					0.00	0.00	0.00	0.00
Stripes											
	4 4" Wide White Stripes	1,161	LF					0.00	0.00	0.00	0.00
	5 12" Wide White Stripes	119	LF					0.00	0.00	0.00	0.00
Totals								0.00	0.00	0.00	0.00